Conversion of Bullock Stalls of the Transport Corps into Sepoys' Quarters Bangalore.

Sl. No.	Items of work	Unit	Quantity
1	Earthwork excavation foundation and filling basement with consolidation.	C. ft.	105
2	Burnt stone in clay foundation and basement ...	„	4,439
3	Burnt brick in clay, superstructure ...	„	7,328
4	Burnt brick in mortar ...	„	543
5	Burnt stone slabs 6" roughly dressed ...	S. ft.	1,239
6	Existing burnt stone slab, fixing to sill of door ways ...	„	414
7	Plastering with chunam ...	Sqr.	233·01
8	Coping over compound wall with brick in clay and chunam plastering, complete.	R. ft.	328
9	Rounding the inner compound wall ...	„	653
10	Teakwood battened door 1/4" thick plank, shutter and iron fittings, complete.	S. ft.	897
11	Junglewood plain plank 1¼" thick, battened door with iron fittings, etc.	„	414
12	Three-forth inch mesh expanded metal ventilators with 3" x 2" thick frames, etc., complete.	„	276
13	Removing and refixing V-shaped burnt stone slab drain...	R. ft.	310
14	Chocolate painting, two coats ...	Sqr.	22·42
15	Tarring, two coats ...	„	32·43
16	Iron pipes, 1½' long 1½" dia. to latrine ...	Each	23
17	Cement drains in bath and open yards ...	No.	46
18	Small V-shaped drain in latrine ...	R.ft.	92
19	Burnt stone slab flooring on 3" concrete bed and cement pointing to latrine and bath rooms.	Sqr.	7·36
20	Constructing pillars for the latrine wall with brick in mortar and cement plastering.	Each	46
21	Removing the lose box drains slabs and stocking ...	„	140
22	Removing the head rape stone with iron rings and stocked.	„	210
23	Patch repairs to walls here and there damaged portions, sides of proposed door way with mortar.	Sqr.	15·00
24	Earthwork, filling in basement level and consolidation ...	C.yd.	92
25	White and colour washing ...	Sqr.	385·00
26	Flooring with gravel including collecting, carting and consolidation, complete.	C.yds.	82
27	Dismantling and removing the existing masonry wall and removing rubbish.	C.ft.	635
28	Unforeseen items during excavation, if found necessary...	L. S.	...
29	Picking and forming the existing road way ...	S.yd.	2,712
30	Collecting, carting and stocking gravel ...	C.yd.	339
31	Spreading and consolidating gravel ...	„	339
32	Collecting, carting and spreading sand ...	„	21

R. W. SCALDWELL,
Executive Engineer.

IN THE COURT OF THE SUBORDINATE JUDGE, MYSORE,

Miscellaneous Application No. 7 of 1927-28.

In the matter of the estate of B. Rachappa ... ... *Deceased.*

Parvathamma, wife of late B. Rachappa, Palace Vidwan, Chaluvamba Agrahar, Mysore ... ... *Applicant.*

Whereas the aforesaid applicant Parvathamma, resident of the aforesaid place, claiming to be the wife of the said B. Rachappa, deceased, has applied to this Court for a certificate under Regulation VII of 1901, to collect debts payable in respect of the estate of the said B. Rachappa, deceased, who died on 17th of June 1927.

Notice is hereby given of the said application, and all claimants in the estate of the said B. Rachappa, deceased, are invited to appear in this Court, on 27th day of September 1927, when the petition of the said Parvathamma, applicant, will be heard and the right to the certificate will be determined.

Given under my hand and the seal of the Court, this 15th day of September 1927.

D. ALASINGRACHAR,
Subordinate Judge.